Confirmed Presumed Summary Report

Client Name: Windsor - ESSEX Community Housing Corporation (CHC)

Building Address: 445 Glengarry Ave

Development: Cameron Montrose

District: 1

Development: Carrieron Montrose District: 1												
SYSTEM	MATERIAL NAME	MATERIAL IDENTIFICATION	MATERIAL DESCRIPTION	LOCATIONS	FRIABILITY	ACCESSIBILITY	TOTAL QUANTITY	UNITS	HAZAROUS CONTENT			
									RESULTS	HAZARD	PRIORITY	ESTIMATED COST
Floor	Vinyl Floor Tiles	VFT1	12"x12" Brown with White Streaks	1312 ,1416 ,1419 ,1511 ,1512 ,1522	N	A	2900	SF	Chrysotile 4%	Confirmed Asbestos	Priority 3	
Floor	Vinyl Floor Tiles	VFT2	12"x12" Beige with Brown and Yellow Specks	10001 ,10002 ,1110 ,1116 ,1117 ,1121 ,1200 ,1207 ,1312 ,1402 ,1411	N	A	2400		Chrysotile 2%	Confirmed Asbestos	Priority 3	
Floor	Vinyl Floor Tiles	VFT3	12"x12" Off- White with Light and Dark Brown Specks	1126 ,1128 ,1200 ,1229 ,1300 ,1329 ,1400 ,1429 ,1500 ,1529 ,1600 ,1629	N	А	8500		Confirmed Asbestos	Confirmed Asbestos	Priority 3	
Floor	Vinyl Sheet Flooring	VSF1	Beige and Brown Square Pattern	1121 ,1207 ,1416 ,1512	N	А	200	SF	Chrysotile 30%	Confirmed Asbestos	Priority 3	
Floor	Vinyl Sheet Flooring	VSF1	Beige and Brown Square Pattern	1511 ,1522	N	E	100	SF	Chrysotile 30%	Confirmed Asbestos	Priority 2	
Walls	Texture Finish	Balcony Texture Finish	Texture Finish found on Balcony	1110 ,1116 ,1117 ,1121 ,1207 ,1312 ,1402 ,1411 ,1416 ,1419 ,1511 ,1512 ,1522	Y	A	500	SF	Chrysotile 4%	Confirmed Asbestos	Priority 3	
Floor	Mastic	Mastic	Mastic under VFT	10001 ,10002 ,10003 ,1110 ,1111, 1111, 1112 ,1207 ,1207 ,1312 ,1402 ,1411 ,1416 ,1419 ,1419 ,1511 ,1512 ,1522 ,1600	N	E	11300	SF	Chrysotile 2%	Confirmed Asbestos	Priority 3	
Piping	Parging Cement Over Fibreglass	Parging Cement over Fibreglass	Parging Cement over Fibreglass	1524	Y	A	8	Each	Chrysotile 65%	Confirmed Asbestos	Priority 1	
Piping	Parging Cement on Fittings	N/A	Parging Cement on Fittings	1524	Y	А	3	Each	Chrysotile 65%	Confirmed Asbestos	Priority 1	