

District Summary Report

| Client Name: Windsor -ESSEX Community Housing Corporation (CHC) | | | | | | | | Building Address: 1323 Tilston Ave | | | |
|--|-------------------|-------------------------|--------------------------------------|--------------|------------|----------------|-------|---|--------------------|------------|----------------|
| Development: Bridgeview I | | | | | | | | District: 2 | | | |
| SYSTEM | MATERIAL NAME | MATERIAL IDENTIFICATION | MATERIAL DESCRIPTION | DEVELOPMENT | FRIABILITY | TOTAL QUANTITY | UNITS | HAZAROUS CONTENT | | PRIORITY | ESTIMATED COST |
| | | | | | | | | RESULTS | HAZARD | | |
| Floor | Vinyl Floor Tiles | VFT1 | 12"x12" Beige with black veins | Bridgeview I | N | 200 | SF | Chrysotile 2% | Confirmed Asbestos | Priority 3 | |
| Floor | Vinyl Floor Tiles | VFT3 | 9"x 9" Black with light brown streak | Bridgeview I | N | 80 | SF | Chrysotile 2% | Confirmed Asbestos | Priority 3 | |
| Ducts | Heat Shield | N/A | Heat Shield | Bridgeview I | Y | 2 | SF | Chrysotile 60% | Confirmed Asbestos | 0 | |
| Ducts | Heat Shield | N/A | Heat Shield | Bridgeview I | Y | 4 | SF | Chrysotile 60% | Confirmed Asbestos | Priority 1 | |
| Ducts | Heat Shield | N/A | Heat Shield | Bridgeview I | Y | 18 | SF | Chrysotile 60% | Confirmed Asbestos | Priority 3 | |

| Client Name: Windsor -ESSEX Community Housing Corporation (CHC) | | | | | | | | Building Address: Various Addresses | | | |
|--|----------------------------|-------------------------|----------------------------|---------------|------------|----------------|-------|--|--------------------|------------|----------------|
| Development: Bridgeview II | | | | | | | | District: 2 | | | |
| SYSTEM | MATERIAL NAME | MATERIAL IDENTIFICATION | MATERIAL DESCRIPTION | DEVELOPMENT | FRIABILITY | TOTAL QUANTITY | UNITS | HAZAROUS CONTENT | | PRIORITY | ESTIMATED COST |
| | | | | | | | | RESULTS | HAZARD | | |
| Walls | Drywall and Joint Compound | N/A | Drywall and Joint Compound | Bridgeview II | N | 16020 | % | Chrysotile 1% | Confirmed Asbestos | Priority 3 | |
| Ceiling | Drywall and Joint Compound | N/A | Drywall and Joint Compound | Bridgeview II | N | 700 | SF | Chrysotile 1% | Confirmed Asbestos | 0 | |
| Ceiling | Drywall and Joint Compound | N/A | Drywall and Joint Compound | Bridgeview II | N | 5090 | SF | Chrysotile 1% | Confirmed Asbestos | Priority 3 | |